

**INTERIOR OF DAHEJ SEZ LIMITED OFFICE AT 605-607, 3RD EYE BUILDING, PANJRAPOLE, AHMEDABAD**

S. No.	Qty.	Description of Item	Rate	Per / Unit	Total Amount
1	AS PER DESIGN	<b>FULL HEIGHT PARTITION</b> Providing and fixing 6 mm thick ply for wooden full partition above clear glass with supports of wooden batons for partition using necessary screws, outside coverage with 1 mm thick wooden lamination and fevicol as directed by engineer-in-charge; the item included all hardware, door openings & fixed type glass openings for windows etc. complete.		Sq.ft.	
2	AS PER DESIGN	<b>LOW HEIGHT PARTITION</b> Providing and fixing 6 mm thick ply for wooden low height partition above clear glass with supports of wooden batons for partition using necessary screws, outside coverage with 1 mm thick wooden lamination and fevicol as directed by engineer-in-charge; the item includes all hardware, door openings & fixed type glass openings for windows etc. complete.		Sq.ft.	
3	AS PER DESIGN	<b>COLUMN &amp; WALL CLADDING</b> Column cladding with wooden panelling etc. complete as per direction of architect in-charge.		Sq.ft.	
4	85.00	<b>ENTRANCE DOOR</b> Providing & fixing 35 mm Thick Shutter for doors, windows and clear-store window including indian teak wood frame of size 10 cm x 7 cm including anodised aluminium butt hinges with necessary screws including alluminium anodised fixtures and fastening and P/A one coat of wood primer and two coats of enamel oil paint of required quality, brand and shade etc. complete as directed by engineer in charge (Full panel).		Sq.ft.	
5	190.00	<b>PARTITION DOOR</b> P/F Wooden Partition Door fully glazed with frosted film 6 mm thick glass complete.		Sq.ft.	
6	4.00	Executive Table with Storage & Drawers (7'6"x3') in ply wood & lamination		Nos.	
7	8.00	Staff Table with Storage & Drawers (5'x2') in ply wood & lamination		Nos.	
8	5.00	Back Side Unit with storage (2'6" Ht.)		Sq.ft.	
9	16.00	Seating (Sofa) (2 & 3 Seater )		Seat	
10	6.00	High back chair Revolving hydraulic system		Nos.	
11	9.00	Medium back chairs Revolving hydraulic system		Nos.	
12	47.00	Staff chairs medium back revolving hydraulic system		Nos.	
13	5.00	Corner Unit for sofa finishes as per table finish		Nos.	
14	67.00	File Racks in wood ply & lamination		Sq.ft.	
15	2.00	Meeting table for 8 persons (8' x 4')		Nos.	
16	1.00	Reception table (12'x1'6")		Nos.	

17	AS PER DESIGN MIN. 1800	<b>FALSE CEILING</b> Providing and fixing false ceiling made of standard G.I. sections and gypsum board sheets/POP inclusive of all hangers, edge members and other clips complete, with sheets fixed with proper Philip screws by power drills and joints duly finished ensuring level in line and plumb to make flat and curved as per design to take finished all paint. All inclusive of making cutouts for light fixtures, ac grills, etc. framework should be conforming to India Gypsum specifications.	Sq.ft.
18	126.00	<b>VERTICAL BLINDS</b> Providing and fixing vertical blinds / roller of standard brand complete with necessary imported runners and fittings etc. complete as directed by engineer-in-charge.	Sq.ft.
19	AS PER SITE CONDITION	<b>VITRIFIED TILES</b> Providing and laying vitrified 8 mm thick (Somany, Nitco, Asian or equivalent) in flooring & skirting laid on a bed of 12 mm thick cement mortar (1 cement : 4 coarse sand) or fixing on existing flooring with mortar or adhesive finishing with flush pointing in white cement.	Sq.ft.
20	1.00	<b>CONSTRUCTION OF NEW PANTRY &amp; REPAIRING OF 3 EXISTING TOILETS, BRICKWORK, DOOR, WINDOWS, VENTILATION, TOILET &amp; OTHER AREAS</b> construction of new pantry, & repairing of 3 existing toilets & other areas including demolition of ex. wall & floors etc. & providing & fixing new brick work with 15 mm thick plaster, fixing of vitrified tiles (Somany, Nitco, Asian or equivalent) floor & coloured glazed tile in dado, fixing of water supply pipe lines, drainage & sanitary fixture approved make or equivalent fixture & sanitary fittings & with Granite Platform for wash basin etc. complete.	Job
21	3860.00	<b>PAINTING</b> Plastic emulsion paint of approved brand and manufacture and of required shade on wall surfaces in even shade, after thoroughly brushing the surface clean, even and sand papered smooth.	Sq.ft.
22	32.00	<b>NEW WINDOWS</b> Providing and fixing three/two track extruded aluminium sliding windows & ventilators of commercial sections of aluminium 1.2 mm thick 18 mm series with sliding shutters with 4 mm thick transparent glass with colour powder coated, fittings and fixtures and transparent silicon sealant glass fixing to frame as per details etc. complete as directed by engineer-in-charge.	Sq.ft.
23	95.00	<b>EXISTING WINDOWS' REPAIRING</b> Repairing of windows & ventilators of commercial sections of aluminium sliding shutters with 4 mm thick transparent glass with colour powder coated, fittings and fixtures and transparent silicon sealant glass fixing to frame as per details etc. complete working as directed by engineer-in-charge.	Sq.ft.
24	1.00	Providing, fixing, installing, testing & commissioning a 12 way TPN distribution board with 1 No. 63 Amps 3 Phase TPN MCB 2 nos. 6 to 32 amp. sp mcb 60 nos, ELCB 40 amp. 6 nos., as per direction of engineer incharge.	Set
25	1.00	Providing, fixing, installing, testing & commissioning 100 amp MCCB with enclosure etc. complete as per direction of engineer incharge.	Nos.
26	1805.00	Electrification work with point wiring including plug points for lights, fans, ac computer LAN cable etc. ( Finolex/polycab/FR or equivalent).	Sq.ft.

27	1.00	Intercom wiring and EPABX System (optima or equivalent).		Job
28	1.00	Electric Fixtures (Havells, Orient, Crompton, Roma or equivalent make). Providing and fixing air conditioners (LG/Voltas/Blue Star or equivalent make) including all electrical fittings with installation etc. complete (A) 1.5 ton split type; 2 star machine etc. complete as directed by engineer-in-charge.		Job
29	7.00	2.0 Ton A.C.		Nos.
30	3.00	1.5 Ton A.C.		Nos.
31	1.00	1.0 Ton A.C.		Nos.
32	11.00	Installation Charge		Nos.
33	120.00	Extra copper tubing		Rft.
34	120.00	Extra drainage		Rft.
35	11.00	Outdoor stands		Nos.
		(Note : 15 ft copper & drainage tube included per unit)		
36		ANY NEW ITEM SUGGESTED BY BIDDER		Job
		TOTAL AMOUNT		