

Name of work: - Repairing work of toilet block (Stair side / LHS) at Admin Building (Toilet) in Dahej SEZ Part-1

For above subject work, invite offer from Pre-qualified contractors.

It is requested to visit the site in consultation with following officials of

DSL.

1. Chirag Limachiya (Site Engineer) Mo.9714033995
2. Bhavin Pancholi (Site Engineer) Mo.8128947892

Please submit the offer in seal cover only after verification of work at site.

Time for site visit: - 3.00 P.M on date.21.04.2023

Subject mention on seal cover as under.

Name of work: - Repairing work of toilet block (Stair side / LHS) at Admin Building (Toilet) in Dahej SEZ Part-1

Address: - Office of Dahej SEZ Ltd.

Dahej SEZ Part-1,

At & Po: - Dahej,

Ta: - Vagra

Dist: - Bharuch

Last date of submission on or before 5:00 PM on Date.28.04.2023

Note:- 1) Only Pre-qualified contractor of Dahej SEZ Ltd. Is eligible to quote / submit

2) Price bid- Agency has to quote the rate including all taxes but without (GST) as per SEZ Act & Rule and invoice is to be raised under GST Act and mentioned "supply to SEZ under LUT/Bond without payment of GST.

Name of work :- Repairing work of toilet block (Stair side / LHS) at Admin Building (Toilet) in Dahej SEZ Part-1

Price Bid

Sr No.	Description	Unit	Qty	Submitted Rate in Figure (Rs.)	Submitted Rate in Words (Rs.)	Total Amount
1	Providing and laying white glazed tiles 6mm thick in flooring trends of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1-cement : 3-coarse sand) finishing with flush pointing in white cement.as per requirement by DSL. (Brand and shade as approved by DSL)	Sq.Mtr	16.00			
2	Toilet Leakage repairing work Repairing of drainage line / Water Supply line in toilet at 1st floor including demolition, Pipe repairing, new pipe fitting, repairing of tile floor, tile fitting, etc.Complete as per instruction give by DSL time to time	JOB	1.00			
3	Pro. And fixing single layer water proof gypsum board 12.5 mm thick sections using water proof board of size 1220 mm x 1830 mm x 8.0 mm suspended by GI suspender channel of size 25 mm x 3 mm with intermediate channel of size 18 mm x 40 mm x 0.8 mm at 1220 mm center to center ceiling section of size 40 mm x 35 mm x 0.55 mm at 457 mm c/c and perimeter channel A of size 20 mm x 27 mm x 30 mm x 0.5 mm at edges & drops incl.paper tap sand sofit cleat, anchor fastener, scotch bolt connecting cleat,joining compound top coat on ceiling incl.making ney,opening for light fitting,diffuser etc. comp. as per detail drawing as directed	Sq.Mtr	100.00			
4	Repairing outside wall of Toilet block which include the work of Cleanig of existing wall, removal of all dust particles, fixing of cement sheet with provision of spacer as approved by DSL . Fixing of plastic sheet, Applying two coat of plastic paint including putty work as per shade of colour approved by DSL etc complete as per the instrctoin of Site Engineer	Sq.Mtr	20.00			

Name of work :- Repairing work of toilet block (Stair side / LHS) at Admin Building (Toilet) in Dahej SEZ Part-1

Price Bid

Sr No.	Description	Unit	Qty.	Submitted Rate in Figure (Rs.)	Submitted Rate in Words (Rs.)	Total Amount
5	Applying two coats of putty & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth.	Sq. Mtr	100.00			
				Total =		

Total Amount : Figure :

Word :

Sign and seal of authority

Note:-

- 1) Please visit the site and submit the Offer / Rate
- 2) DSL reserve the right to increase / decrease scope of work /Item/Quantity as decided by DSL Authority.
- 3) If agency fails to submit LUT then payment will process as per SEZ Act & Rule.

Place :-

Date :-